BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24207

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Providing Gym Equipments in ward no 11 (Kuvempunagar) in Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Nataraj T	
				In Figures	In Words
1	10	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	270.0	Rupees Two Hundred Seventy Only
2	27	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	190.0	Rupees One Hundred Ninety Only
3	18.75	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	Rupees Five Thousand Only
4	20.25	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4000.0	Rupees Four Thousand Only
5	12.15	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	Rupees Five Thousand Only
6	54	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	90.0	Rupees Ninety Only
7	18	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5500.0	Rupees Five Thousand Five Hundred Only
8	2	The chest press is a heavy guage steel made up of 100 mm NB MS pipe the sub structure consists of 25mm NBMS pipes and heavy duty bushes pivoted to 1 end and moveable up down in other. The easts are made up of pressed sheet metal of heavy guage self weighted machine built to supports as vigorous wok out for upto 2 people the equipment hosts one of the most basic and effective body stength exercises. The chest press supports and promotes upbody strength and strengthens and the triceps pectoralis, and deltoids in the pressing moton the exercise can be done n repetitions stating off with 5 to 15 repetition and building the above equipment duly powder coated etc complete as per specifications and directions of engineer in charge of the work	Nos	224000.0	Rupees Two Hundred Twenty Four Thousand Only

Signature of the contractor

Executive Engnieer

No.	Approved Qty.	Description	Unit	Approved Tender Rates of Nataraj T	
				In Figures	In Words
9	2	TSAI 1139A the AIR WALKER made up of D100mm NBMS pipes the substructures consists of 40 mm NBMS pipe and heavy duty bushes pivoted to 1 end and in walking motion the foot steps is made up pressed sheet metal of heavy guage it provides to side by side exercises position which deliver cardiavascular vacular benifits by simulating the runing motion although with straighter eegs and no impact. The exercises completly the avoids the impact stress runners often experiences on feet knees, bips and lower back many people cannot tolerate the jarring motion of jogging walking is a good alternative but it does not stretch are fully activate the important muscule in the upper thigh the air walker improves both cardiovascular fitness and fiexibility exercise levels can be of 5 to 15 munites duration experiment with various peed and different levels of stretch the above equipment is duly powder coated etc complete as per specifications and directions of engineer in charge of the work	Nos	140000.0	Rupees One Hundred Forty Thousand Only
10	2	TSI 1140 A - The FUN RIDER made up of 100mm NBMS pipe the such structure conisits of 40mm NBMS pipes and heavy duty bushes pivoted to one end and movable in materal motion the eseat is made up of pressed sheet metal of heavy guage fun rider station involves cardiovasular benedits using a rowing motion This apparatus promotes strengthening the biceps latissmus dorsi and rear deltoids in the pulling motion white also developing cardiovascular fitness, Exercise levels can be of 5 to 15 minutes duration, expreiments with various sppeds and different levels of intensity The above equipment is duly powder coated etc complete as per specifications and directions of engineer in charge of the work	Nos	130000.0	Rupees One Hundred Thirty Thousand Only
11	2	TSI 8155 C The STANDING RORATION made up of 100mm NBMS pipe the sub structure consists of 32 mm NBMS pipe and heavy duty bearing and bushes provided to ensure smooth plate rotation the standing plates are made up of pressed sheet metal of heavy guage it benches in stretching the internal and external obliques and adding emphasis on the abdomitals and extesor muscles of the spine. The above equipment is duly powder coated etc complete as per specifications and directions of engineer in charge of the work	Nos	130000.0	Rupees One Hundred Thirty Thousand Only
12	2	The ROWER the structue consists of 25 & 20mm NB MS pipes and heavy duty bushes pivot to one end and movable back and front rowing motion it invilves cardiovascular bebefits using a rowing motion. This apparatus promotes stengthening the bicep latissimus dorsi and rear deltoids in the pulling motion while also developing cardiovascular fitness exercise levels can be of 5 to 15 minutes duration Experiement with various speeds and different level of intensity The above equipment duly powder coated etc	Nos	115000.0	Rupees One Hundred Fifteen Thousand Only
13	2	The SPINNERS made up of 100 mm NB NS pipe. The sub structure consists of 25 & 20mm NB MS pipe and heavy duty bearing and bushes provided to ensure smooth wheel rotation. They have large rotary wheel with adjustable resistance. The exercise employs the full flexibility around the shoulder and the many muscles that raise and power the arms and provide shoulder stability work the apparatus in various directions and stances The Tai Chi Spinners can be installed at a variety of heights making it perfect for all ages. The above equipment is duly powder coated etc complete as per specifications	Nos	155000.0	Rupees One Hundred Fifty Five Thousand Only
14	2	ROPE PULLER the ROPE PULLER made up of 100mm NB MS pipe the sub structure consists of 32 mm NB MS pipes and heavy duty provided to ensure smooth rope transition these are a primary indicator of upper body stength the exercises place more emphasision the stretching improving the grip introduce yourselft at all exercises gradually avoiding undue stress slowly build the number of repetitions the above equipment is duly powder coated etc complete as per specifications and directions of engineer in charge of the work	Nos	77000.0	Rupees Seventy Seven Thousand Only
15	4	Providing and fixing Dust Bins as per designs, Drawing, Specification and Direction of Engineer in charge of Work	Cum	4300.0	Rupees Four Thousand Three Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

05/04